





BRIDGERLAND VILLAGE, PLAT "G" PHASE 1

PART OF THE NORTH HALF OF THE SOUTHEAST QUARTER OF SECTION 19,
TOWNSHIP 14 NORTH, RANGE 5 EAST OF THE SALT LAKE BASE AND MERIDIAN
14.29 acres

SCALE: 1" = 100'



CURVE	LENGTH	RADIUS	TANGENT	CHORD	DELTA	BEARING
C1	64.87	625.00	32.47	64.85	5°56'50"	S78°29'12"W
C2	248.57	625.00	125.95	246.93	22°47'13"	N87°08'42"W
C3	37.33	80.00	19.01	36.99	26°44'14"	N62°22'58"W
C4	23.92	25.00	12.96	23.02	54°48'58"	N21°36'23"W
C5	71.07	75.00	38.45	68.44	54°17'25"	N32°56'49"E
C6	103.00	71.22	62.86	94.25	82°51'43"	S77°15'45"E
C7	22.39	25.00	12.01	21.65	51°18'28"	S12°29'27"W
C8	63.18	55.00	35.59	59.76	65°49'08"	N05°14'07"E
C9	67.95	55.00	25.62	46.45	49°52'20"	N52°39'06"W
C10	64.02	55.00	36.19	60.47	66°41'26"	S69°01'31"W
C11	78.05	55.00	47.23	71.66	81°18'12"	S04°58'18"E
C12	18.11	55.00	9.14	18.03	18°52'02"	S55°03'26"E
C13	22.40	25.00	12.01	21.65	51°19'40"	N38°49'37"W
C14	49.54	117.65	25.14	49.18	24°07'49"	S36°46'11"E
C15	145.68	117.65	83.83	136.55	70°56'45"	S81°20'34"E
C16	92.93	80.00	52.51	87.80	66°33'33"	N15°44'05"W
C17	118.44	125.00	64.08	114.06	54°17'25"	N32°56'49"E
C18	54.62	25.00	48.21	44.39	128°11'02"	S68°23'37"W
C19	127.72	130.00	69.55	122.65	56°17'29"	S20°52'07"E
C21	62.23	70.00	33.34	60.20	50°56'16"	S23°33'06"E
C24	19.09	70.00	9.61	19.03	15°37'40"	S09°43'32"W
C25	23.90	130.00	11.68	23.27	10°16'04"	S12°24'40"W
C26	336.52	675.00	172.90	334.98	28°44'03"	N89°52'53"E
C27	60.66	130.00	30.89	60.12	26°44'14"	S62°22'58"W
C28	325.98	650.00	166.49	322.57	28°44'03"	S89°52'53"W
C29	49.00	105.00	24.95	48.55	26°44'14"	N62°22'58"W
C30	94.75	100.00	51.27	91.25	54°17'25"	N32°56'49"E
C31	149.07	93.32	95.84	133.72	91°31'35"	S73°59'44"E
C32	121.98	105.00	68.92	115.23	66°33'33"	N15°44'05"W
C33	52.28	45.00	29.54	49.39	66°33'56"	S15°44'17"E



- 30' SET BACK FOR FRONT AND BACK YARDS 10' SET BACK FOR SIDE YARDS
- 10' WIDE PUBLIC UTILITY EASEMENT AS SHOWN
- STORM RUN OFF WILL BE DISCHARGED ON THE LOT OWNER'S LAND OR INTO EXISTING NATURAL DRAINAGE CHANNELS.
- CULINARY WATER WILL COME FROM THE RESERVOIRS LOCATED ABOVE PLAT "C".
- FIRE HYDRANTS REQUIRED IN PHASE I ARE CAPABLE OF PRODUCING 500 GPM AT 20 PSI.
- ALL LOTS HAVE THE MINIMUM ONE ACRE REQUIRED BY THE STATE BOARD OF HEALTH FOR SEPTIC TANKS.
- TOTAL ACREAGE: PHASE I - 14.29 ACRES

NOTES

I, LAYNE SMITH, DO HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR, AND THAT I HOLD CERTIFICATE NO. 334561, AS PRESCRIBED UNDER THE LAWS OF THE STATE OF UTAH. I FURTHER CERTIFY THAT BY THE AUTHORITY OF THE OWNERS, I HAVE MADE A SURVEY OF THE TRACT OF LAND SHOWN ON THIS PLAT AND DESCRIBED BELOW, AND HAVE SUBDIVIDED SAID TRACT INTO LOTS AND STREETS, HEREINAFTER TO BE KNOWN AS BRIDGERLAND VILLAGE PLAT "G", PHASE 1, AND THE SAME HAS BEEN CORRECTLY SURVEYED AND ALL STREETS ARE THE DIMENSIONS SHOWN.

LAYNE J. SMITH

BOUNDARY DESCRIPTION

BRIDGERLAND VILLAGE, PLAT "G", PHASE 1 GARDEN CITY, UTAH PROJECT # 05-106

PART OF THE NORTH HALF OF THE SOUTHEAST QUARTER OF SECTION 19, TOWNSHIP 14 NORTH, RANGE 5 EAST OF THE SALT LAKE BASE AND MERIDIAN, DESCRIBED AS FOLLOWS:

BEGINNING NORTH 00°28'27" WEST, ALONG THE EAST LINE OF SECTION 19, 1317.46 FEET AND NORTH 89°40'34" WEST ALONG THE SOUTH LINE OF THE NORTH HALF OF THE SOUTHEAST QUARTER OF SAID SECTION 19, 2075.23 FEET FROM THE SOUTHWEST CORNER OF SECTION 19, TOWNSHIP 14, RANGE 5 EAST OF THE SALT LAKE BASE AND MERIDIAN;

AND THENCE NORTH 89°40'34" WEST, 618.48 FEET TO THE EAST LINE OF PHASE 2, OF PLAT "F", OF BRIDGERLAND VILLAGE, AS RECORDED IN THE OFFICE OF THE RICH COUNTY RECORDER;

THENCE NORTH 00°25'42" WEST, ALONG SAID EAST LINE OF PHASE 2, OF PLAT "F", 744.54 FEET TO THE SOUTH LINE OF PHASE 3, OF PLAT "F", AS RECORDED IN THE OFFICE OF THE RICH COUNTY RECORDER;

THENCE NORTH 75°30'52" EAST, 225.29 FEET;

THENCE 338.52 FEET ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 675.00 FEET, INCLUDED ANGLE OF 28°44'03" AND A LONG CHORD THAT BEARS NORTH 89°52'53" EAST, 334.98 FEET;

THENCE 60.66 FEET ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 130.00 FEET, INCLUDED ANGLE OF 26°44'14" AND A LONG CHORD THAT BEARS SOUTH 62°22'58" EAST, 60.12 FEET;

THENCE SOUTH 49°00'52" EAST, 319.75 FEET;

THENCE 127.72 FEET ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 130.00 FEET, INCLUDED ANGLE OF 56°17'29" AND A LONG CHORD THAT BEARS SOUTH 20°52'07" EAST, 122.65 FEET;

THENCE 23.30 FEET ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 130.00 FEET, INCLUDED ANGLE OF 10°16'04" AND A LONG CHORD THAT BEARS SOUTH 12°24'40" WEST, 23.27 FEET;

THENCE SOUTH 17°32'41" WEST, 165.05 FEET;

THENCE SOUTH 23°45'11" WEST, 72.49 FEET;

THENCE SOUTH 40°58'45" WEST, 283.35 FEET BACK TO THE POINT OF BEGINNING;

CONTAINING 14.29 ACRES

- SURVEY NARRATIVE:**
- BASIS OF BEARING FOR THIS SURVEY IS NORTH 00°28'27" WEST ALONG THE EAST LINE OF SECTION 19, TOWNSHIP 14 NORTH, RANGE 5 EAST, SALT LAKE BASE AND MERIDIAN (FOUND IN BRASS CAP)
 - THE PURPOSE OF THIS SURVEY IS TO DIVIDE A PORTION OF THE NORTH HALF OF THE SOUTHEAST QUARTER OF SECTION 19 SUBDIVIDED AS SHOWN.
 - RETRACEMENT: WESTERLY LINES ARE THE EAST LINE OF PHASE 2, PLAT "F", BRIDGERLAND VILLAGE FROM FOUND MARKERS AND RECORD DIMENSIONS; PART OF THE NORTH LINE BY THE SOUTH LINE OF PHASE 3, PLAT "F", BRIDGERLAND VILLAGE FROM FOUND MARKERS AND RECORD DIMENSIONS; SOUTH LINE IS THE SOUTH LINE OF THE NORTH HALF OF THE SOUTHEAST QUARTER OF SAID SECTION 19.
 - 5/8" X 24" REBAR AND CAPS TO BE PLACED FOR LOT CORNERS.

OWNER/SUBDIVIDER:
NAME: TED WILSON
ADDRESS: 135 SOUTH MAIN
ADDRESS: LOGAN, UTAH
PHONE: (435) 755-3006

No.	REVISION	DATE

Skyline A/E/S, INC.
Architecture / Engineering / Surveying
96 W. Golf Course Rd. #101, Logan, UT 84321
(435) 762-8601 / Fax (435) 762-8697

Project Title:
BRIDGERLAND VILLAGE
P.O. BOX 314
GARDEN CITY, UTAH

Sheet Title:
PLAT "G", PHASE 1
FINAL PLAT

Drawn By: T. WESTON	Project Number: 05-106	Sheet No.:
Designed By: T. WESTON	Date: 10 JAN 2006	1
Reviewed By: L. SMITH	Sheet Scale: 1" = 100'	1 of 1

HEALTH DEPARTMENT APPROVAL

THE CULINARY WATER SYSTEM AND WASTE DISPOSAL SYSTEM SHOWN ON THIS PLAT ARE APPROVED.

DATE: May 12, 2006
District Health Dept.

PLANNING COMMISSION APPROVAL

APPROVED THIS 16th DAY OF June A.D., 2006
BY THE Planning Commission.

CHAIRPERSON

ENGINEER'S CERTIFICATE

I CERTIFY THAT I HAVE EXAMINED THIS PLAT AND FIND IT TO BE CORRECT AND IN ACCORDANCE WITH THE INFORMATION ON FILE IN THIS OFFICE.

DATE: 6-2-06
ENGINEER

OWNER'S DEDICATION

KNOW ALL MEN BY THESE PRESENTS THAT WE, THE UNDERSIGNED OWNERS OF THE ABOVE DESCRIBED TRACT OF LAND, HAVING CAUSED THE SAME TO BE SUBDIVIDED INTO LOTS AND STREETS TO BE HEREAFTER KNOWN AS BRIDGERLAND VILLAGE PLAT "G", PHASE 1, DO HEREBY FILE SAID SUBDIVISION WITH DEDICATION OF PUBLIC UTILITY EASEMENTS AS INDICATED TO UTILITY PROVIDERS, BUT WITHOUT DEDICATION OF STREETS, ALLEYS, COMMON AREAS, OR OTHER PUBLIC PLACES.

IN WITNESS WHEREOF WE HAVE HERETO SET OUR SIGNATURES THIS 15th DAY OF May A.D., 2006
Bridgerland Village, Inc.

Ted J. Wilson President
Dixie Wilson Secretary

TOWN BOARD APPROVAL AND ACCEPTANCE

PRESENTED TO THE GARDEN CITY COUNCIL THIS 20th DAY OF June A.D., 2006, AT WHICH TIME THIS SUBDIVISION WAS APPROVED AND ACCEPTED.

Mayor: Kammie Wilson
Date: June 20, 2006

COUNTY RECORDER'S No. 68759

STATE OF UTAH, COUNTY OF RICH, RECORDED AND FILED AT THE REQUEST OF TOWN OF GARDEN CITY
DATE: 06/26/06 TIME: 11:32 AM FEE: 39.00
ABSTRACTED

Book: FID Page 411
INDEX FILED IN: FILE OF PLATS
COUNTY RECORDER

APPROVAL AS TO FORM

APPROVED AS TO FORM THIS 20th DAY OF June A.D., 2006

ATTORNEY

CORPORATE ACKNOWLEDGMENT

STATE OF Utah
COUNTY OF RICH

ON the 15th day of May, 2006, PERSONALLY APPEARED BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC IN AND FOR SAID COUNTY OF RICH, IN SAID STATE OF UTAH, AND AFTER BEING DULY SWORN, ACKNOWLEDGED TO ME THAT Ted J. Wilson and Dixie Wilson OF SAID CORPORATION AND THAT THEY SIGNED THE OWNER'S DEDICATION FREELY, VOLUNTARILY AND IN BEHALF OF SAID CORPORATION AND FOR THE PURPOSES THEREIN MENTIONED.

MY COMMISSION EXPIRES 3/19/2010
Marilyn J. Adams NOTARY PUBLIC

Ted J. Wilson President
Dixie Wilson Secretary